MARYLAND HISTORICAL TRUST DETERMINATION OF ELIGIBILITY FORM

NR Eligible:	yes	_
	no	

Property Name: National Guard Armory	Inventory Number: SM-463
Address: 23250 Hollywood Road Md. Rt. 245 City: Leonardtown	Zip Code: 20650
County: St. Mary's USGS Topographic Map:	Leonardtown Quad
Owner: Maryland Military Department Is	the property being evaluated a district? No X yes
Tax Parcel Number: 44 Tax Map Number: 121 Tax Account ID N	Number: 03-015025
Project:Agen	ncy:
Site visit by MHT Staff: X noyes Name:	
Is the property located within a historic district?yesNo X	
If the property is within a district District In	ventory Number:
NR-listed districtyes Eligible districtyes District Nar	ne:
Preparer's Recommendation: Contributing resourceyesno Non-	-contributing but eligible in another context
If the property is not within a district (or the property is a district) Preparer's Recommendation: Eligible X yesno	
Criteria: X A B X C D Considerations: A Documentation on the property/district is presented in: The St. Mary's County Historical Society, the Lexington Park Library, Dedication Program for the National Guard Armory December 11, 1954 Description of Property and Eligibility Determination: (Use continuation sheet if new Maryland Guard Armory in Leonardtown is one of three are Maryland during the Cold War era. Completed in 1954, it is located (Maryland Route 245) on the outskirts of Leonardtown. Calvert (1953-54) and Charles (1948) counties.	excessary and attach map and photo) The mories constructed in Southern ocated on the Hollywood-Leonardtown
Lawrence P. Sangston of Baltimore was the architect furnished Leonardtown armories. MARYLAND HISTORICAL TRUST REVIEW Eligibility recommended Eligibility not recommended Criteria: A B C D Considerations: A Comments:	
Davisona ND Davison	Pote Date

200600061

MARYLAND HISTORICAL TRUST NR-ELIBILITY REVIEW FORM

Continuation Sheet No. 1

SM-463

The Leonardtown Armory is a two-story masonry building set on a concrete foundation. The central bay of the front façade is covered with sandstone panels. The brick is laid in five course American bond. The sandstone elements of the exterior feature Art Deco style detailing.

The main façade faces west and is seven bays wide with a slightly projecting central bay clad in sandstone. The central bay features a stepped parapet finished with sandstone coping. The sandstone slab above the door features an arrow motif that is repeated in the lighting fixtures that bracket the doors. A flagpole is positioned on each side of these lights. Recessed modern glass double doors have replaced the heavy wood doors that were originally on the building. A six-light metal window is located above the doors. The sandstone coping continues around the roof edge of the entire building.

The main bay is flanked on both sides by secondary bays, each containing three windows on the first and second floors. The windows on the first story are seated over continuous concrete bases that run along the first story of the remaining elevations. Attached to each side of the main block are one-story two bay wings.

The one story wing on the south elevation contains a set of double metal doors with six lights reinforced by metal mesh. The lower halves of both doors are louvered. A metal window is located to the right of the double doors and a second one-panel metal door is located to the right of the window. Attached to the rear of the one-story wing on this elevation is the vehicle storage area. The garage entrance is clad in sandstone panels and features a stepped parapet identical to the one on the main entry. The vehicle entry door has been removed and filled in with cement block painted red to match the building's brick, and the National Guard name panel above the door has been removed. The lintel above the door opening features the same arrow motif as that on central bay of the main elevation. Two metal bomb points are imbedded on either side of the threshold. The flanking bays each contain a one panel wood door on the first floor and one window opening on the second story. Each of the windows contains four lights and is protected by metal bars.

The rear, east elevation is the back wall of the drill hall. The asphalt-shingled gambrel roof of the drill hall rises above the flat roof on the front of the building. On this elevation all but two of the original seven windows on the second story have been bricked up. The remaining two are identical to the windows on the south elevation. Also visible at the northern end of this elevation is the one story wing. New glass and metal doors have been added to this wing to serve as a second entrance into the library. This wing remains separate from the library space and once was an indoor shooting range for the National Guard. Today the Election Commission stores voting machines there. Three metal windows covered with bars and chain link pierce the one-story wing on this elevation.

MARYLAND HISTORICAL TRUST NR-ELIBILITY REVIEW FORM

Continuation Sheet No. 2

5M-463

The north elevation of the one story wing features two metal windows and a metal door on the end closest to the main elevation.

History

The Maryland National Guard took part in the D-Day invasion of Normandy during World War II, landing at Omaha Beach. As the Cold War escalated in the late 1940s and fear of nuclear attack was a national concern, National Guard units throughout the United States were called upon to remain at the ready in case of a national emergency.

A unit of the Maryland National Guard was functioning in St. Mary's County by the late nineteen forties. The first organizational meeting for the National Guard was sponsored by the American Legion, which wanted to recruit young men for a new locally based unit. Colonel Claypool of the Second Army came to the county to aid in the process. In 1947, Colonel Claypool contacted National Guard Captain James Raley of Leonardtown and asked him to take command of an Engineer Company in the town. Captain Raley visited local communities and presented talks at high schools about the benefits of being a guardsman. A group was put together and held its first drill in the gym of Leonard Hall School on November 19, 1947. The next step would be the construction of a local armory.

According to Mr. William R. Riley, Director of Installations for the Maryland Military Department, the Calvert and Leonardtown armories were constructed because of lobbying by then Maryland Senator Louis Goldstein of Calvert County. His constituents, who were active in the National Guard at that time, had to travel to the Washington area for their monthly training. They complained about the hardship of commuting such a long distance. Although Adjutant General of the Maryland National Guard, Milton Record, was opposed to the construction, Goldstein won out.

Adjutant General Record decided to make Southern Maryland the recruiting area for the engineer battalions. St. Mary's Company B, 121st Engineer Battalion (C) was raised in 1948. The company drilled at various facilities in St. Mary's, chief among them the Charlotte Hall Military Academy, which was established before the Revolutionary War, and the Leonard Hall Military Academy. The Leonardtown Armory was constructed in 1953 and opened December 11, 1954 with a dedication ceremony. The Charlotte Hall Military Academy band played the national anthem, and State Senator Paul J. Bailey was the master of ceremonies. Major General Henry C. Evans and other National Guard officers delivered remarks. The Honorable Milton A. Record, Adjutant General, State of Maryland delivered the dedication address.

MARYLAND HISTORICAL TRUST NR-ELIBILITY REVIEW FORM

Continuation Sheet No. 3


SM-463

Festivities included a dinner and dance for invited guests and an open house the next day. The new armory housed Company "B" 121 Battalion (C) of the Maryland National Guard. The program from the ceremony, decorated with the Battalion Insignia, lists the young men from Leonardtown and the county at large who were enlisted Guardsmen. The site functioned as a National Guard Armory from 1954 to 1979.

Decommissioned as a National Guard Armory in 1979, the building is leased to St. Mary's County by the Maryland Military Department. In the early 1980s, the first floor was used as county office space, and the second floor served as a dormitory for work release prisoners. After the floor space was reconfigured, the Leonardtown branch of the St. Mary's County Memorial Library moved into the first floor in 1984. The second story became home to the St. Mary's County Archives in 1989. The archives have since relocated, and the second floor now serves as administrative space for the library.

The Leonardtown National Guard Armory and its counterparts in Calvert and Charles County are a part of the history of the Cold War era in rural Southern Maryland. The armory is eligible for the National Register under Criterion A: because it is associated with events that have made a significant contribution to the broad patterns of our history. It also fits Criterion C because it embodies the distinctive characteristics of a type and period of construction.

Prepared by:	Date Prepared:





SM-463 National Guard Armorg, Leonardtown St. Mary's County, MD August 2005 W elevation main facale MD SHPO Photo: Teresa Wilson



SM-463 National Guard Armory, Leonardtown St. Mary's County Hugust 2005 MD SHPO w.elev. KIND THE DOIS ON Photo: Teresa Wilson



5m-463 National Guard Armany, Leonardtown St. Mary's County MD August 2005 W elevation MD SHPO PRO 2019 S EN 2652 0 N N N+1-40 AC+03 ACs-04 SA110 GR08 Z126.3/100.0 Photo: Teresa Wilson



SM-463 National Guard Armory Leonarchown St Mary's County August 2005 South elev. MD SHPO Photo: Teresa Wilson



SM-463 Nation of Guard Armiry, Leanardtown St. Mary's County August 2005 MD SHPO South elev Photo: Teresi Wilson



SM-463 National Guard Armory, Leonardtown ·St. Mary's County MD SHPO August 2005

Photo: Teresa Wilson



Sm-463 National Guard Armony, Leonardtown St. Mary's County MD SHPO East Elev August 2005 photo: Teresa Witson



SM-4:3 National Guard Arming Learnitown St Mary's County EANAUNT 2005 mo SHPO Phiti: Teresi William

MARYLAND NATIONAL GUARD LEONARDTOWN ARMORY

1953 - 1954

BOARD OF PUBLIC WORKS

THEODORE R MCKELDIN

COVERED TO THE STATE OF THE STA

MILITARY DEPARTMENT

DEPARTMENT OF PUBLIC IMPROVEMENTS
NATEAN 1 SWITE
LIBRENCE P SANGSTON PRINCIPAL AREE

CONTRACTOR

SMI- 463 Notrinal Guard Armory, Leonardtown Plague in Lobby August 2005 MIS SHPO Photi: Terlis Wilson



3M-43 National Evard Amory, Leonordown St May's County Lobby August 2005 H. H. 1-13 AC+03 AC-04 SALIO GROS 2126.37100.0 1/0/ Photo: Teresa Wilson



SM-463 National Guard Annory Leonardhum St Mary's County MD SHPO August 2005 2 822 N N N-4 29 PC+83 PC=-84 SPT 18 CR88 2126.37189.8 1/11 Photo: Teresa Wilson